



महाराष्ट्र जीवन प्राधिकरण

मुख्य अभियंता, पुणे प्रादेशिक विभाग, पुणे

ISO ९००१:२००८ Cert. Reg. No.RQ११/८८३७

नवीन प्रशासकीय इमारत, पुणे लष्कर पा.पु.केंद्र आवार,

४६३ स्टेवली रोड, सेंट मेरी चर्च शेजारी, कॅप, पुणे-४११ ००१

दूरध्वनी : -०२०-२९७०६०६४ email : cemjppn@gmail.com

जा.क मु.अ.(पुणे) चि.शा/ दरसूची/ ५४९० /२०२१

दिनांक ३०/०८/२०२१

शुद्धीपत्रक क्र. २

विषय :- मजीपाच्या सन २०२१-२२ च्या राज्य दरसूचीतील काही बाबींचे वर्णन सुधारित करणेबाबत


संदर्भ :- अधीक्षक अभियंता, महाराष्ट्र जीवन प्राधिकरण मुंबई यांचे प.क्र. अअ(मु)/EP-३७(२०२०) ६०५ दि. ११.०८.२०२१

मजीपा दरसूची सन २०२१-२२ च्या प्रस्तावास मध्यवर्ती कार्यालयामार्फत मान्यता देण्यात आली असून ती अध्यक्ष दरसूची समिती तथा मुख्य अभियंता, पुणे यांचेमार्फत प्रसिद्ध करण्यात आली आहे. प्रसिद्ध करण्यात आलेल्या दरसूचीमध्ये काही बाबींच्या वर्णनामध्ये दुरुस्ती, सुधारणा करणे आवश्यक असून त्याबाबतचे शुद्धीपत्रक खालीलप्रमाणे .

अ.क्र.	बाब क्र	पान क्र.	च्या ऐवजी	असे वाचावे				
१	८	१०	Genaral Notes Following increase in % over normal schedule of rates of M.J.P. for 2021-22 will be applicable. (Ref. PWD GR. No. DSR/1091/CR-6577/Planning-3,dated 08/07/2003).	Genaral Notes Following increase in % over normal schedule of rates of M.J.P. for 2021-22 will be applicable. (Ref. PWD GR. No. DSR/1091/CR-6577/Planning-3,dated 08/07/2003).				
			Sr. No	Area	% Increase	Sr. No	Area	% Increase
			--	--	--	i	Rajbhavan	20%
			--	--	--	j	For Naxalite Area (Notified)	10%
२	३१	११	General Notes The royalty charges are considered in the rate analysis of CSR 2021-22 As per Government Resolution No. Rev and forest Dept Gaukhani 10/1009/ Pra.Kra. 309/ Kha. Mantralaya dt.11.2.2010.	General Notes The royalty charges are considered in the rate analysis of CSR 2021-22. As per the Government of Maharashtra, Revenue and Forest Departments Gazette No.67 Dt. 15 May 2015				

अ.क्र.	बाब क्र	पान क्र.	च्या ऐवजी	असे वाचावे
३	४	११६	Providing supplying in standard length (PE material) HDPE Double wall corrugated pipe for non pressure underground drainage and sewerage with smooth internal & corrugated external surface confirming to IS 16098:Part-2 2013 with spigot or plain end with necessary jointing material coupler including transportation and freight charges, inspection charges, loading and unloading charges, conveyance to departmental store and stacking the same in closed shade duly protecting from direct sun ray and rains excluding GST levied by Gol and GoM in all respect, etc. complete.	Providing supplying in standard length (PE material) Structured-Wall plastic piping system for Non-pressure underground drainage and sewerage with smooth internal & corrugated external surface confirming to IS 16098:Part-2 2013 with spigot or plain end with necessary jointing material coupler including transportation and freight charges, inspection charges, loading and unloading charges, conveyance to departmental store and stacking the same in closed shade duly protecting from direct sun ray and rains excluding GST levied by Gol and GoM in all respect, etc. complete.
४	५	११६	Lowering, Laying and Jointing (PE material) HDPE double wall corrugated pipe for non-pressure underground by heating to the ends of pipes with the help of tefflon coated electric heater to the required temperature and then pressing the ends together against each other, to form a monolithic & leak proof joint by thermosetting process. The pressing may be required to be done with Jacks/ Hydraulic Jacks/Butt fusion machine etc. complete with all materials labours as directed by Engineer - in - charge. including	Lowering, Laying and Jointing (PE material) Structured-Wall plastic piping system for Non- pressure underground drainage and sewerage underground by heating to the ends of pipes with the help of tefflon coated electric heater to the required temperature and then pressing the ends together against each other, to form a monolithic & leak proof joint by thermosetting process. The pressing may be required to be done with Jacks/ Hydraulic Jacks / Butt fusion machine etc. complete with all materials labours as directed by Engineer - in - charge.

अ.क्र.	बाब क्र.	पान क्र.	च्या ऐवजी	असे वाचावे
५	६	११७	Item wording Hydraulic testing of HDPE double wall corrugated pipe for non pressure underground line to specified pressure including cost of all materials and labour and water for testing for specified length including cutting, placing end cap making arrangement for filling safe water using reciprocating type pumps which should be able to provide specified test pressure gauges and other necessary equipments, labour, operation charges, etc. required for testing. The rate under this item shall also include cost of retesting, if necessary and reinstating to original position	Item wording Hydraulic testing of Structured-Wall plastic piping system for Non-pressure underground drainage and sewerage underground line to specified pressure including cost of all materials and labour and water for testing for specified length including cutting, placing end cap making arrangement for filling safe water using reciprocating type pumps which should be able to provide specified test pressure gauges and other necessary equipments, labour, operation charges, etc. required for testing. The rate under this item shall also include cost of retesting, if necessary and reinstating to original position


(सु.ब.भुजबळ)

अध्यक्ष, दरसुची समिती तथा
मुख्य अभियंता (प्र)

मजीप्रा प्रादेशिक विभाग पुणे

प्रत : - मा. मा.सदस्य सचिव, महाराष्ट्र जीवन प्राधिकरण मुंबई यांना माहीतीसाठी सविनय सादर

प्रत : - मुख्य अभियंता, महाराष्ट्र जीवन प्राधिकरण ठाणे/ नाशिक/ औरंगाबाद/ अमरावती/ नागपुर यांना माहीतीसाठी अग्रेषित

प्रत : - अधीक्षक अभियंता (मुख्यालय) / अधीक्षक अभियंता मध्यवर्ती नियोजन, संकल्पचित्र व सनियंत्रण कक्ष, महाराष्ट्र जीवन प्राधिकरण मुंबई यांना माहीतीसाठी.

प्रत : -उप अभियंता, अद्यावत तंत्रज्ञान कक्ष, मजीप्रा, मुंबई यांना माहीतीसाठी व मजीप्राच्या संकेतस्थळावर upload करण्यासाठी